

Guyana Motor Racing & Sports Club

Bill of quantity

Casting of 150mm/6" thick concrete slab

Concrete slab 30 meters length by 6 meters width

Payment will be done base on measure works completed

item	Description of work required	unit	QTY	Amount
1	Supply all skill, semi -labor tools and equipment transportation of workers to cast 150mm concrete slab. Work includes. Fabrication and installation of steel & form works, (#65 BRC placing of construction plastic/ membrane preparation of sub base (but not limited to cut fill and compact with plate compactor), pour and compact 150mm concrete to fair finished apply 1 coat of concrete curing compound chemical with a spray can, all works must be done to the club's technical personal satisfaction. all material will be provided by GMR&SC. area must remain clean after all work is completed by contractor	m ²	1	

Approved by GMR&SC

Guyana Motor Racing & Sports Club

Bill of quantity

Casting of 200mm/8'' thick by 1.2 meters/4' height by 150-meter/492' length concrete safety walls

And concrete footing 1.2 meters/4' width by 200mm/8'' thick by 150 meter/ 492' length

Payment will be done base on measure works completed

item	Description of work required	unit	QTY	Amount
1	Supply all skill, semi -labor tools and equipment transportation of workers to cast sloid concrete safety wall. Work includes. Fabrication and installation of 12mm double cage steel work. Fabrication of form works including all struts, tie and brace, excavation of 18''x 4ft trenching for footing. Installation of 4'' dia pvc pressure for drainage and 2'' galvanize pipes as fence post at (6 to 8 ft) intervals all works must be done to the club's technical personal satisfaction. all material will be provided by GMR&SC. area must remain clean after all work is completed by contractor	m	1	

Approved by GMR&SC.